

ADDENDUM

January 30, 2020

Addendum No. 4

Town of Windsor
Department of Public Works
Building Window Replacement and Renovations Project
Windsor, CT 06095

CSA No. 19-01

1. Additional Clarification: Window Sill Steel – The flat plate is 24” long spaced 24” apart (36” O.C.). The plate is to be bolted to the existing angle. The head angle bracket spacing is 48” O.C.
2. Existing partitions where shown to remain will not have the drywall removed for installation of M.R. type.
3. The new knee wall in cafeteria 108 is on all 3 sides of the room.
4. The millwork in the cafeteria is to be removed by G.C. Different millwork provided by owner to be installed by G.C.
5. Page 25 of the Towns Bid Form was not deleted. Sub-Contractors shall be listed.
6. The ceiling hts vary from 8’ to 11’ Tallest in Admin. 101.
7. The Ceilume Soniguard suspended ceiling insulation gets 2 pieces of 24”x24” per each 24”x48” ceiling tile.
8. Removal of existing vinyl tile was answered in Addendum #3.
 - A. Toilet ceramic tile flooring is to be removed for installation of new.

January 29, 2020

CSA No. 19-01

Receipt of this Addendum shall be acknowledged on the Bid Form. This Addendum shall be made part of the Contract Documents.

END OF ADDENDUM

c: file

\\Lisa\c\CSA_LISA\PROJECTS\05files\05-11-EHCHC-150 N. Main St. Manch\Bid Forms\0511_Addendum 01.doc

Capital Studio Architects

1379 Main Street • East Hartford, Connecticut 06108
860.289.3262 fax 860.289.3163
capitalstudios.net

Addendum No. 1 / 1 of 1