#### TOWN OF WINDSOR

# REQUEST FOR QUALIFICATIONS & FEE PROPOSAL FOR DESIGN OF ENGINEERING FOR SLAB MOISTURE MITIGATION

#### SAGE PARK MIDDLE SCHOOL 25 SAGE PARK ROAD WINDSOR, CT 06095

Proposals Due: TUESDAY NOVEMBER 22, 2022 by 11:00 a.m.

Finance Office Attn: James Bourke Windsor Town Hall Finance Department Second Floor 275 Broad Street Windsor, CT 06095

### TOWN OF WINDSOR SLAB MOISTURE MITIGATION & ENGINEERING EVALUATION DESIGN CONSTRUCTION DRAWINGS

THIS IS A REQUEST FOR BIDS AND THE TOWN RESERVES THE RIGHT TO NEGOTIATE AND CONTRACT WITH ANYONE OR NO ONE IN THE BEST INTERESTS OF THE TOWN OF WINDSOR.

**WEDNESDAY OCTOBER 26,2022** 

#### INTENT AND GENERAL INFORMATION

The Town of Windsor solicits proposals from qualified consulting Architect Engineering firms to provide design services for the SLAB moisture mitigation repairs and improvements to SAGE PARK MIDDLE SCHOOL 25 SAGE PARK ROAD in Windsor, CT. 06095

The SCOPE OF WORK of this project is to address; EVALUATE EXISTING SLAB MOISTURE REPORTED ISSUES TO SECTIONS of the 1994 ADDITION SLAB FLOORING OF THE BUILDING.

All work performed under the contract between the Town of Windsor and the firm selected who shall be a professional Architect Engineering firm licensed by the State of Connecticut.

#### SUBMISSION AND DEADLINE

The respondent shall submit eight (8) sets of their proposal c/o:

James Bourke Director of Finance Windsor T own Hall 275 Broad Street Windsor, CT 06095

Bids will be received at the Finance Department Second Floor Windsor Town Hall until Tuesday November 22, 2022 11:00 AM at which time they will opened in the Town Hall, Room TBD, and publicly read aloud. Results will be posted on town web site later that day.

The Windsor Public Building Commission has full responsibilities for Windsor regarding this project.

Contact Whit Przech at 860-285-1870 with any questions and to schedule any site visits.

Whit Przech Building and Facilities Manager Town Hall 275 Broad Street Windsor, CT 06095

#### SCOPE OF SERVICES

The effected slab areas are located in the 1994 addition of 59,885 sq. ft. to this building. Issues are; water seeping up through the slab, compromised vct flooring adhesion, Gymnasium wood flooring buckling, odors and safety concerns for students and staff.

The selected Architect Engineer will provide comprehensive architectural and engineering services for the existing moisture issues and the design of resolution(s) to these moisture in slab issues. Submit a itemized fee proposal for the following services;

- 1. Slab moisture Investigation Testing Monitoring Fee.
- 2. Schematic Conceptual Design Drawings Specifications Phase Fee.
- 3. Upon Approval of Line (two) 2. Final Construction Drawings Specifications Fee.
- 4. Bids Review with town Staff Fee.
- 5. Construction Administration Fee.
- 6. All Project As-Builts All Project Documents Closeout Fee.

The awarded architect engineering firm will work closely with Board of Education and town staff to define a finite scope of work.

The selected architectural engineering firm must have sufficient staff to assure prompt delivery of services and completion of assigned tasks. The selected architect must possess a Professional Engineer licensed by the State of Connecticut to be responsible for the management and design.

#### **SELECTION CRITERIA**

The Architect Engineering firm may be selected and / or interviewed by the Windsor Public Building Commission on the basis of the following:

- Experience and knowledge with the design of similar moisture mitigation projects.
- Displayed understanding of this project's required scope of work.
- Design and Administration approach to the project requirements.
- Experience with design build single point of responsibility is a consideration
- Previous experience with Windsor Public Building Commission Projects.
- All Firms submitted fee(s) for design and administrative services cost.
- Lump sum price on enclosed bid form with signed Non-Collusion form.
- Awarded firm will attend Monthly PBC meetings to update Commissioners on Project Progress. Review approve all contractor payments any Change Orders for submission to the PBC.

#### TERMS AND CONDITIONS

Unless otherwise modified, the following Terms and Conditions will apply to an agreement which may result from this process. The Architect Engineer may use a standard AIA form of agreement incorporating the following provisions.

#### Services to be Provided

The Architect shall provide services as set forth in the RFP proposal and in accordance with the terms identified herein. The services provided will be performed on behalf of and solely for the Town of Windsor and any information, tests, reports, correspondence, and conclusions shall not be released to other parties unless authorized by the Town of Windsor or in accordance with any applicable state or federal law.

#### **Billing and Payment**

The Town of Windsor will pay the Architect for services performed in accordance with a signed Agreement. Invoices will be submitted periodically or upon completion of services rendered. The Town reserves the right to request substantiating information on any bill submitted. The Town will, within 30 days after receipt of an invoice requesting payment and review and approval by the Windsor Public Building Commission (PBC), either indicate the approval of payment and process the invoice or indicate to the Architect in writing, the reason for refusing to approve said invoice. In the latter case, the Architect will make the necessary corrections and resubmit the invoice. The Town will, within 30 days of an approved invoice, pay the amount to the Architect.

#### **Court Litigation and Waiver of Jury Trial**

Notwithstanding the existence of any provision for arbitration of disputes in the contract or any legislation providing for arbitration, any dispute arising under this contract shall not be submitted to arbitration and the parties shall be left to the remedies at law. It is further expressly agreed that both parties waive and relinquish their right to a trial by jury of any dispute arising out of this contract. The intent of the parties is not to have a jury decide any aspect of any dispute which may arise under this contract.

#### **Equitable Relief**

Nothing herein shall prevent either party from obtaining a court order enforcing the mediation process or such other temporary or equitable relief until such time that the dispute is settled or finally adjudicated.

#### Insurance

The Architect shall, after being awarded the Contract but prior to starting work, furnish Certificates of Insurance, including Automobile, Commercial General Liability, Professional Liability, Umbrella Liability, and Worker's Compensation insurance in the following amounts:

#### 1. Commercial General Liability Insurance:

The Architect shall provide Commercial General Liability insurance with a combined single limit of \$1,000,000 per occurrence, \$1,000,000 aggregate for bodily injury and property damage.

The CGL shall be written on ISO occurrence form CG 00 01 10 93 (or a substitute form providing equivalent coverage) and shall cover liability arising from premises, operations, independent contractors, products-completed operations, personal injury and advertising injury, and liability assumed under an insured contract (including the tort liability of another assumed in a business contract)

#### 2. Commercial Automobile Liability Insurance

The Architect shall provide Commercial Automobile Liability insurance with a combined single limit of \$1,000,000 per occurrence, \$1,000,000 aggregate, and shall include coverage for all owned, hired, and non-owned vehicles.

#### 3. Worker's Compensation Insurance

The Architect shall provide Worker's Compensation Insurance in the required amount as applies to the State of Connecticut and Employers Liability Insurance as follows:

Bodily Injury by Accident - \$100,000 each accident

Bodily Injury by Disease - \$500,000 policy limit

Bodily Injury by Disease - \$100,000 each employee

#### 4. Umbrella Liability Insurance

The Architect shall provide Commercial Umbrella Liability insurance with a combined single limit of \$1,000,000 per occurrence, \$1,000,000 aggregate for bodily injury and property damage.

#### 5. **Professional Liability Insurance**

The Architect shall provide Professional Liability insurance with a combined single limit of \$1,000,000 per occurrence, \$1,000,000 aggregate for bodily injury and property damage.

Each Policy of Insurance shall include a waiver of subrogation in favor of the Town of Windsor and shall provide no less than thirty- (30) days' notice to the Town of Windsor in the event of a cancellation or change in conditions or amounts of coverage. The

Commercial General Liability, Automobile, and Umbrella Liability shall name the Town of Windsor as an additional insured.

Certificates of Insurance, acceptable to the Town of Windsor shall be delivered to the Town of Windsor prior to the commencement of the work and kept in force throughout the term hereof.

The above insurance requirements shall also apply to all Sub-consultants and the Architect shall not allow any Sub-consultants to commence work until the Sub-consultants insurance has been so obtained and approved.

#### USE OF ARCHITECTS DRAWINGS, SPECIFICATIONS AND OTHER DOCUMENTS

The paper or electronic drawings, specifications and other documents prepared by the Architect for this Project shall be the joint property of the owner and the Architect, provided, however, the rights of ownership shall be limited as follows:

The Owner shall have the unlimited right to submit or distribute documents to meet official regulatory requirements or for similar purposes in connection with the project.

#### FORM OF NON-COLLUSIVE AFFIDAVIT

### DESIGN OF ENGINEERING FOR SLAB MOISTURE MITIGATION SAGE PARK MIDDLE SCHOOL

State of		
County of		
	_, being first duly swe	orn, deposes and says:
has not, in any manner, directly of communication or conference, with other bidder, or to fix any overhead any other bidder, or to secure any	uch proposal or bid is olluded, conspired, con, to put in a sham or indirectly, sought be the any person, to fix ad, profit or cost elengy advantage against	s genuine and not collusive or onnived or agreed, directly or bid or to refrain from bidding, and by agreement or collusion, or the bid price or affiant or of any nent of said bid price, or of that of
Signature (Signature should be n	_ otarized)	Printed Name and Title
Name of Company/Corporation	_	Date
be his free act and deed as such		_, and acknowledged the same to , and the free act and deed
of said corporation before me.		
In Witness Whereof, I hereunto s	et me hand and seal	l.
	Notary Public My Commiss	

#### **BID FORM**

# REQUEST FOR QUALIFICATIONS & FEE PROPOSAL DESIGN OF ENGINEERING FOR SLAB MOISTURE MITIGATION SAGE PARK MIDDLE SCHOOL 25 SAGE PARK ROAD WINDSOR, CT. 06095

To: Mr. James Bourke, Director of Finance
Town of Windsor
275 Broad Street
Windsor, CT 06095

Pursuant to and in compliance with your "Request for Proposals" relating thereto, the undersigned,

(Name of Firm)

Having visited the site and carefully examined existing conditions and RFQ/RFP documents received prior to the scheduled closing time for recipient of Bids to the Town of Windsor, 275 Broad Street Windsor, Ct 06095, hereby agrees as follows:

For design services for the;

DESIGN OF ENGINEERING FOR SLAB MOISTURE MITIGATION TO SAGE PARK MIDDLE SCHOOL 25 SAGE PARK ROAD in Windsor, CT. 06095

If awarded this contract, Windsor Public Building Commission will execute an AIA contract with the awarded Architectural Firm.

Signed Non-Collusion form attached \_\_\_\_\_

#### ITEMIZED FEE LIST

Slab moisture Investigation Testing Monitoring Fee	
2. Schematic Conceptual Design Drawings Specifications Phase Fee.	
3. Upon Approval of Line (two) 2. Final Construction Drawings Specifications Fee.	
4. Bids Review with town Staff Fee	
5. Construction Administration Fee	
6. All Project As-Builts All Project Documents Closeout Fee.	
TOTAL PROPOSAL LUMP SUM COST FOR ALL FEES LISTED IN THIS RFQ;	
(written) (\$	)



September 23, 2021

Mr. Chuck Waterfield Physical Plant Manger Windsor Public Schools 601 Matianuck Ave. Windsor, CT 06095

RE:

Slab Moisture Investigation

Sage Park Middle School, 25 Sage Park Road, Windsor, CT

Fuss & O'Neill Reference No. 20160987.A60

Dear Mr. Waterfield:

Fuss & O'Neill, Inc. (F&O) has completed our evaluation of the existing concrete slab-on-grade at the Sage Park Middle School in Windsor, CT. The 178,000 square-foot school was originally constructed in 1972 and has subsequently undergone several renovations and additions. While F&O has not conducted an independent evaluation of the property, it appears to be located in an area with a presumed high groundwater table. The purpose of this evaluation was to investigate the as-built condition of the first-floor slab and test the concrete for compressive strength and relative humidity. It is our understanding that the existing finishes for portions of the 1st floor of the building have repeatedly had issues remaining adhered to the concrete slab-on-grade and have been replaced in the past without success. Additionally, a moisture barrier was applied on the top side of the slab and did not prevent moisture from impacting the flooring.

The purpose of this investigation was to determine the as built condition of the existing concrete slab-on-grade and perform compressive and relative humidity tests to determine its strength and moisture content. Based on the results of this testing, as presented below, we have developed recommendations for next steps to address the moisture problem.

146 Hartford Road Manchester, CT 06040 † 860.646.2469 800.286.2469 f 860.533.5143

It is our understanding that most of the areas of concern were part of a significant renovation/addition that occurred in 1992. F&O was able to review select original design drawings from this work and it appears that the concrete slab-on-grade was intended to be 4 inches thick with 4 inches of compacted base material below and a 6 mil vapor barrier below the base material. The original slab design for the gym was not available for our review.

#### www.fando.com

Califomia
Connecticut
Maine
Massachusetts
New Hampshire
Rhode Island

Vermont

F&O performed a site visit on August 17, 2021 with Independent Materials Testing Lab (IMTL) to review the condition of the existing concrete slab-on-grade, extract cores for compressive strength testing, and install relative humidity sensors. IMTL returned to the site 24 hours after this initial site visit to record the relative humidity levels at each location and remove the sensors. Three rooms were selected for compressive strength testing and six rooms were selected for installing the

F:\P2016\0987\A60\Deliverables\Report\Letter Report.docx

Corres.



Mr. Chuck Waterfield September 23, 2021 Page 2

relative humidity sensors as indicated in the table below. Generally, the exposed sections of the cat-in-place concrete slab appear to be in good condition with no obvious indications of deterioration or structural distress. We did note that the slab, in some locations, does appear to be damp; however, no evidence of vapor or water was observed.

#### Results

The results for each room are summarized in the table below.

Room	Slab Depth (in)	Compressive Strength (psi)	Relative Humidity (%)		
GYM	4.5	6,010	99		
110	3.0	5,190	99		
111	-	-	99		
115	-	-	99		
117	_	-	99		
118	3.0	6,820	99		

The results of the testing indicate that the as-built concrete slab-on-grade for the rooms that were part of the 1992 addition and renovation does not comply with the minimum design thickness of 4 inches. Our visual observations indicated that there is base material below the slab; however, its thickness and the presence of a vapor barrier below it could not be verified.

#### Discussion

While there isn't a maximum value for relative humidity (RH) in a concrete slab-on-grade, the conditions noted previously (repeated detachment of floor coverings and localized buckling of the gym floor) are more likely to occur at higher RH values. Many flooring manufacturers will limit the RH in a concrete slab to 75% to 80% in order for their flooring material and its adhesive to properly bond to the slab. The results of the RH tests conducted as part of this evaluation are much higher than this threshold and are likely the main contributing factor in the flooring's repeated failure to successfully adhere to the concrete slab. The higher RH values could be attributed to the high groundwater table.

Based on the results of this analysis, it is very likely that the pre-existing high groundwater table as well as the variance in the as-built concrete slab thickness with respect to its intended design are contributing factors to the measured RH values. It does not appear that the RH of the slab has affected its structural performance or durability. It is possible that the vapor barrier below the base material that is directly below the concrete slab has either failed, was installed incorrectly (or not at all), or is not sufficient given the high groundwater table. It is likely that the vapor barrier and the additional thickness of the concrete slab are helping to keep the RH of the slab from exceeding the



Mr. Chuck Waterfield September 23, 2021 Page 3

values observed during this evaluation. Generally, a 6-inch to 8-inch thick layer of course, free draining gravel or crushed stone below the slab is recommended under high ground water conditions to create a capillary break and minimize the effect of hydrostatic pressure and the ingress of water. The design drawings called for 4 inches of compacted slab base course which may or may not be sufficient.

Other factors that may contribute to the migration of groundwater into a concrete slab-on-grade include the seams/overlaps between adjacent sections of the vapor barrier, the water-to-cement ratio of the as-built concrete slab-on-grade, the presence of water reducing and/or waterproofing admixtures in the concrete mix, and the conditions under which the slab was cured. These factors could not be investigated based on the information available to F&O at the time of this investigation.

#### Recommendations

Based on the results of the concrete tests, our review of the original design drawings, and our observations of the as-built construction, it is clear that the high groundwater table is having a significant effect on relative humidity and moisture content of the existing concrete slab-on-grade. These conditions have led to the floor finishes failing to adhere to the slab. Managing the high groundwater elevation is a significant undertaking that will likely involve invasive and costly measures. Potential options to mitigate the high groundwater table include the following:

- Installing a raised flooring system above the current finished floor that prevents the moisture from getting to the new, higher top of slab elevation.
- Installing a new drainage system below the current slab-on-grade that collects
  groundwater before it reaches the slab and directs it outside the footprint of the existing
  building.
- Installing a groundwater reduction system (typically be means of mechanical pumping) to lower the natural groundwater elevation in the immediate area surrounding the building.

We do not recommend coating the existing slab with a liquid applied vapor or moisture barrier and installing new flooring as the some observed conditions are likely to repeat over time.



Mr. Chuck Waterfield September 23, 2021 Page 4

Please contact us with any questions or concerns regarding the investigation and test results for the concrete slab-on-grade at the Sage Park Middle School in Windsor, CT.

Sincerely,

Jason J. LeDoux, P.E. Senior Project Manager

Enclosures:

Photos

Test Reports



#### Sage Park Middle School – Slab Investigation



Photo 1: Gym Floor Test Area




Photo 2: Typical Classroom Test Area



**Concrete Coring Report** 

	lient:		B	_	0- O2NT-:11	т		n .				100	air)
C	nem:			Fuss c	& O'Neill,	inc.		Proje	ect No.:			518	35
Project:			Sage Park Middle School			Repo	Report No.:			002			
Date Concrete Placed:			Unknown				Repo	Report Date:			08/25/2021		
								Revis	sed:		0	9/08/2021*	**
Da	ate Core C	Obtained:		08/17/	/2021			Lab 7	Γime / Dat	e Placed in		10:10 a	m
Cored by Whom:			Spenc	Spencer Roy			Seale	Sealed Bags:			08/20/2021		
	OCATION				s, 110, 118	3, Gym			Cores Tes			08/25/202	
Lab Technician:			Jason	Jason Norton				_ Time Cores Tested:			8:30 am		
Date of Capping:			8/23/2021			Age o	of Concret	ity in co <del>Luby</del> R	Unknown				
Core ID	Lab No	Length as Drilled	Time Drilled/ Placed in Bag	Sawed Length (in)	Capped Length (in)	Dia. (in)	Wt. (lbs)	Density (lbs / ft³)	Area, Sq. Inches	Failure Load (lbs)	Comp. Strength (psi)	Corrected Strength (psi)	Break Type
Gym	387488	4.5	1.30 nm	4.50	1 75	2 02	170	150 2	12.01	72100	(010	5530	CO.

Average Core Diameter\* 3.22

4.50

2.90

2.95

Nominal Maximum Aggregate Size: 3/4"

4.5

3.0

3.0

1:30 pm

2:00 pm

2:15 pm

Load applied to horizontal plane of concrete as placed for slab coring of concrete as placed for wall coring.

Unless Stated Otherwise:

387488

387489

387490

Gym

Rm 110

Rm 118

1. Cores tested in accordance with ASTM C-42. 2. Cores fractured normally.

4.70

1.52

1.60

150.3

139.0

144.9\*

3. Cores were free of obvious defects.

4.75

3.20

3.25

3.92

2.88

2.87

4. Wet prep used to cut core ends.

72190

33781

44120

6010

5190

6820

5530

4650

6140

S2

S2

S2

12.01

6.51

6.47

Test Method Exceptions: If core dia. less than 3.7" state reason: Four inch cores.

Cores Correction Factors Used

387488 1.21 / .920 387489 1.11 / .896 387490 1.13 / .901

\*\*Report Revision: Updated Density for Core Id Rm 118



pc: Jason LeDoux, P.E., Fuss & O'Neill, Inc.

km



#### **Relative Humidity of Concrete Slabs**

Client:

Fuss & O'Neill, Inc.

Project No.:

5185

Project:

Sage Park Middle School

Report No.:

004

Inspector:

Spencer Roy

Date Cast:

Unknown

Contractor:

Unknown

Date Set:

8/17/2021

Subject:

Relative Humidity of Concrete Slabs

Date Tested:

8/18/2021

The following is a report of relative humidity in Concrete Floor Slabs Using in situ Probes. These tests were conducted in accordance with ASTM F 2170. This test method covers the quantitative determination of percent relative humidity in concrete slabs for field or laboratory tests. The tests were conducted utilizing a Wagner Rapid RH 4.0 Easy Reader. Each test location was prepared and allowed to stand for 24 hours to achieve moisture equilibrium within the test holes.

Upon Installation:

Air Temp. 67°F

CONCRETE SLAB APPROXIMATE THICKNESS: 4"

Test No.	Location	Serial #	Depth from Top of Slab (in.)	RH in Concrete (%)	Temp in Concrete (°F)	Air Temp (°F)
1	Room 111	L620056729	1.5"	99	73	68
2	Room 115	L620058775	1.5"	99	71	68
3	Room 117	L620058794	1.5"	99	73	68

#### Instrument Used

Make, Model, Serial Number RH Rapid Reader



pc: Jason LeDoux, P.E., Fuss & O'Neill, Inc.

rmk

