

PLANT LIST -

NOTES

- NOTES:


 1. IF ANY DISCREPANCIES OCCUR BETWEEN THE AMOUNTS SHOWN ON THE PLAN AND THE PLANT LIST, THE PLAN SHALL DICTATE.
 2. PROPOSED PLANTING BEDS SHALL BE EXCAVATED TO A DEPTH OF 12 INCHES AND FILLED WITH A MIXTURE OF 80% TOPSOIL AND 20% PEAT MOSS. ALL PLANTING BEDS SHALL BE MULCHED WITH 4 INCHES OF 3/4 STONE, WOOD CHIPS OR WOOD BARK MULCH.
 3. ADJUSTMENTS IN THE LOCATION AND/OR NUMBER OF PROPOSED PLANTS MAY BE NECESSARY DUE TO FIELD CONDITIONS. SUCH ADJUSTMENTS SHALL BE APPROVED BY THE DESIGN ENGINEER AND THE TOWN PLANNER.

TREES

SYMBOL	QUANTITY	BOTANICAL NAME	COMMON NAME	SIZE (MINIMUM)
AP	4	<i>ACER PALMATUM DISSECTUM</i>	CUTLEAF JAPANESE MAPLE "CRIMSON QUEEN", "EVER RED" OR SIMILAR CULTIVAR. USE SAME CULTIVAR ALONG FRONT OF BUILDING.	5 GALLON CONTAINER
AR	14	<i>ACER RUBRUM 'RED SUNSET'</i>	RED SUNSET RED MAPLE	3"-3 1/2" CAL. B&B
CC	5	<i>CERCIS CANADENSIS</i>	FOREST PANSY EASTER REDBUD	2"-2 1/2" CAL. B&B
CF	4	<i>CORNUS FLORIDA 'RUBRA'</i>	PINK FLOWERING DOGWOOD	2"-2 1/2" CAL. B&B
CK	8	<i>CORNUS KOUZA</i>	KOUZA DOGWOOD	2"-2 1/2" CAL. B&B
PA	10	<i>PICEA ABIES</i>	NORWAY SPRUCE	6'-8' TALL B&B
PG	14	<i>PICEA GLAUCA</i>	WHITE SPRUCE	6'-8' TALL B&B
PN	5	<i>PRUNUS x 'NEWPORT'</i>	NEWPORT PLUM	1 1/2"-2" CAL. B&B
QP	2	<i>QUERCUS PALUSTRIS</i>	PIN OAK	3"-3 1/2" CAL. B&B
SR	9	<i>SYRINGA RETICULATA 'IVORY SILK'</i>	IVORY SILK TREE LILAC	2"-2 1/2" CAL. B&B

SHRUB

SYMBOL	QUANTITY	BOTANICAL NAME	COMMON NAME	SIZE (MINIMUM)
BG	4	<i>BUXUS x 'GREEN MOUNTAIN'</i>	GREEN MOUNTAIN BOXWOOD	5 GALLON CONTAINER
CP	8	<i>CHAMEACYPARIS PISIFERA 'GOLDEN MOP'</i>	GOLDEN MOP FALSE CYPRESS	3 GALLON CONTAINER
IC	12	<i>ILEX CRENATA 'HETZII'</i>	JAPANESE HOLLY	5 GALLON CONTAINER
RA	16	<i>RHODODENDRON AGLO</i>	AGLO RHODODENDRON	3 GALLON CONTAINER
RPJM	8	<i>RHODODENDRON PJM</i>	PJM RHODODENDRON	3 GALLON CONTAINER
PP	4	<i>PICEA PUNGENS 'MONTGOMERY'</i>	HOOPSII SPRUCE	5 GALLON CONTAINER
TO	2	<i>THUJA OCCIDENTALIS 'SMARAGD'</i>	EMERALD GREEN ARBORVITAE	6'-8' TALL B&B



Sheet
C3.1

THE LOCATIONS OF UNDERGROUND UTILITIES ARE APPROXIMATE AND ALL UTILITIES MAY NOT BE SHOWN. PRIOR TO CONSTRUCTION, CONTRACTOR SHALL CALL 1-800-922-4455 AND HAVE UTILITIES MARKED ON THE GROUND.

Condyne Capital Partners, LLC

Site Plan Prepared for *Layout and Landscaping Plan*

WINDSOR, CONNECTICUT

REVIEWS


D. 934





RS
CUT

1

FT.

۱۷





GRAPHIC SCALE
(IN FEET)
1 inch = 40 ft.


THE LOCATIONS OF UNDERGROUND UTILITIES ARE APPROXIMATE AND ALL UTILITIES MAY NOT BE SHOWN PRIOR TO CONSTRUCTION. CONTRACTOR SHALL CALL 1-800-922-4455 AND HAVE UTILITIES MARKED ON THE GROUND.

SITE PLAN
PREPARED FOR
Condyne Capital Partners, LLC
GRADING AND UTILITIES PLAN
WINDSOR, CONNECTICUT

205 BAKER HOLLOW ROAD

Sheet
C4.1

REVISION
5-2-2023 REVISE FOREBAY AT SOUTH BASIN
DATE



TO THE BEST OF MY KNOWLEDGE AND BELIEF THIS MAP IS SUBSTANTIALLY CORRECT AS NOTED HEREON.

L.S. NO. 9344

NOT VALID WITHOUT A LIVE SIGNATURE AND EMBOSSED SEAL.


Alford
ASSOCIATES, INC.

CIVIL ENGINEERS
WINDSOR, CONNECTICUT
WILSON M. ALFORD, JR., P.E. & L.S.



DATE: APRIL 20, 2023

SCALE: 1 IN. = 40 FT.

P: C21012 D: C22015SP FOLDER: Thrill OJ - Baker Hollow 2022 Hebebrand



N/F SPONZO ENTERPRISES LLC
#800 MARSHALL PHELPS RD



TO THE BEST OF MY
KNOWLEDGE AND BELIEF
THIS MAP IS SUBSTANTIALLY
CORRECT AS NOTED HEREON.

L.S. NO. 9344




NOT VALID WITHOUT A LIVE
SIGNATURE AND EMBOSSED SEAL



CIVIL ENGINEERS
WINDSOR, CONNECTICUT
•
WILSON M. ALFORD, JR., P.E. & L.S.

DATE: APRIL 20, 2023


SCALE: 1 IN. = 40 FT.






THE LOCATIONS OF UNDERGROUND UTILITIES ARE APPROXIMATE AND ALL UTILITIES MAY NOT BE SHOWN PRIOR TO CONSTRUCTION. CONTRACTOR SHALL CALL 1-800-922-4455 AND HAVE UTILITIES MARKED ON THE GROUND.

SITE PLAN
PREPARED FOR
Condyne Capital Partners, LLC
GRADING AND UTILITIES PLAN
WINDSOR, CONNECTICUT
205 BAKER HOLLOW ROAD


Sheet
C4.2







REVISION
DATE



TO THE BEST OF MY KNOWLEDGE AND BELIEF
THIS MAP IS SUBSTANTIALLY CORRECT AS NOTED HEREON.

L.S. NO. 9344

NOT VALID WITHOUT A LIVE SIGNATURE AND EMBOSSED SEAL

Alford
ASSOCIATES, INC.

CIVIL ENGINEERS
WINDSOR, CONNECTICUT




WILSON M. ALFORD, JR., P.E. & L.S.

DATE: APRIL 20, 2023

SCALE: 1 IN. = FT.


SITE PLAN
PREPARED FOR
Condyne Capital Partners, LLC
SITE NOTES AND DETAILS
WINDSOR, CONNECTICUT

205 BAKER HOLLOW ROAD








Sheet
C6.1

TEMPORARY & PERMANENT EROSION CONTROL BLANKETS



PLACE A BIODEGRADABLE EROSION CONTROL BLANKET ON SLOPES 3:1 AND GREATER (INCLUDING THE SLOPES OF THE DRAINAGE SWALE). WHEN INSTALLING, ENSURE THAT THE LAP JOINTS ARE SECURE, ALL EDGES ARE PROPERLY ANCHORED AND ALL STAKING/StAPLING PATTERNS FOLLOW THE MANUFACTURER'S RECOMMENDATIONS.

DETAIL OF TEMPORARY OUTLET PIPE AT WATER QUALITY BASIN #2



STORM DRAINAGE MAINTENANCE SCHEDULE -

MAINTENANCE OF THE ON-SITE STORM DRAINAGE IS THE RESPONSIBILITY OF THE OWNER OF THE PROPERTY.

Maintenance Schedule:

- PARKING AREA SURFACE CLEANING; ALL PAVED AREAS SHALL BE SWEEP ANNUALLY BETWEEN APRIL 1st AND JULY 1st.

CATCH BASINS: ALL BASIN RIM AREAS AND SUMPS SHALL BE KEPT CLEAR OF SEDIMENT, TRASH AND DEBRIS. ALL CATCH BASINS SHALL BE INSPECTED ANNUALLY BETWEEN MAY 1st AND SEPTEMBER 15th AND SUMPS SHALL BE CLEANED WHEN THE DEPTH OF ACCUMULATED MATERIAL EXCEEDS 1 FOOT. ACCUMULATED SAND, DIRT AND DEBRIS SHALL BE DISPOSED OF OFF-SITE IN A PROPER MANNER.

- STORM DRAINAGE PIPES AND STRUCTURES; ALL STORM DRAINAGE STRUCTURES AND PIPES SHALL BE KEPT IN PROPER WORKING CONDITION.

- WATER QUALITY BASINS AND SWALES: BASINS AND SWALES SHALL BE INSPECTED ANNUALLY FOR EVIDENCE OF EROSION. UNDERCUT OR ERODED AREAS SHALL BE REPAIRED WITHIN 30 DAYS OF DOCUMENTATION.

- REFER TO THE LATEST EDITION OF THE CONNECTICUT GUIDELINES FOR STORMWATER QUALITY MANAGEMENT, AS WELL AS THE TOWN'S STORMWATER MANUAL AS AMENDED, AND THE TOWN'S ENGINEERING STANDARDS AND SPECIFICATIONS AS AMENDED, FOR THE PROPER IMPLEMENTATION OF STORMWATER MANAGEMENT.

GENERAL NOTES FOR NARRATIVE -

1. A PRE-CONSTRUCTION MEETING SHALL BE HELD WITH THE TOWN ENGINEER PRIOR TO THE START OF CONSTRUCTION.
2. ALL SOIL STABILIZATION SHALL BE COMPLETED WITHIN FIVE (5) DAYS OF CLEARING OR INACTIVITY IN CONSTRUCTION.
3. A STOCKPILE OF CRUSHED STONE, GEOTEXTILE SILT FENCE AND HAY BALES IS TO BE MAINTAINED ON SITE FOR USE DURING HEAVY RAINS OR OTHER EMERGENCIES.
4. GEOTEXTILE SILT FENCE SHALL BE KEPT ON-SITE IN THE EVENT OF AN EMERGENCY OR TOWN REQUEST FOR ADDITIONAL EROSION PROTECTION DURING CONSTRUCTION.
5. MAINTAIN DUST CONTROL BY USE OF CALCIUM CHLORIDE AND/OR WATER AT ALL TIMES DURING CONSTRUCTION.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CLEANING OF NEARBY STREETS OF ANY DEBRIS AND SEDIMENTS FROM THE CONSTRUCTION ACTIVITIES.
7. ACCUMULATED SEDIMENT SHALL BE REMOVED AS REQUIRED TO KEEP SILT FENCE FUNCTIONAL. IN ALL CASES, DEPOSITS SHALL BE REMOVED WHEN THE ACCUMULATED SEDIMENT HAS REACHED ONE-HALF ABOVE THE GROUND HEIGHT OF THE FENCE.
8. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL", CONNECTICUT DEP BULLITAN 34.
9. THE EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CONSIDERED AS MINIMUM REQUIREMENTS. THE TOWN RESERVES THE RIGHT TO AMEND THE EROSION AND SEDIMENTATION CONTROL MEASURES AS FIELD CONDITIONS WARRANT.
10. ALL CONSTRUCTION, STORMWATER MANAGEMENT AND EROSION AND SEDIMENTATION CONTROLS SHALL COMPLY WITH THE TOWN OF WINDSOR'S "STORMWATER MANAGEMENT ORDINANCE".

11. THE CONTRACTOR AND/OR OWNER SHALL BE CONTACTED IN THE EVENT OF EMERGENCY EROSION OR SEDIMENTATION FAILURE.

12. AFTER A RAIN STORM, HAY BALES, GEOTEXTILE SILT FENCE AND VEGETATIVE COVER SHALL BE INSPECTED FOR POSSIBLE DAMAGE OR WASHOUT. REPAIR AS NECESSARY.

13. NO STUMPS SHALL BE BURIED ON THE SUBJECT PROPERTY.

14. WHEN ACTIVITIES HAVE STOPPED, DISTURBED AREAS MUST BE SEDED WITH PERENNIAL RYE GRASS OR SIMILAR GROUND COVER.

EROSION AND SEDIMENTATION CONTROL NARRATIVE -

1. THE SUBJECT PROPERTY IS APPROXIMATELY 20.6 ACRES OF VACANT POST-AGRICULTURAL LAND LOCATED TO THE SOUTH OF BAKER HOLLOW ROAD IN WINDSOR, CONNECTICUT. AN UNNAMED PERENNIAL STREAM, TRIBUTARY TO MILL BROOK FLOWS SOUTHERLY ALONG THE EASTERN BORDER OF THE PROPERTY. THERE ARE WETLANDS LOCATED ON THE SUBJECT PROPERTY THAT ARE ASSOCIATED WITH THE STREAM. THE PROPERTY IS ZONED INDUSTRIAL (I). LAND USE IN THE VICINITY OF THE PROPERTY IS PREDOMINATELY LIGHT INDUSTRIAL, INCLUDING A RECENTLY BUILT DISTRIBUTION-WAREHOUSE FACILITY IMMEDIATELY TO THE WEST.

2. THE PROPOSAL IS TO CONSTRUCT A 185,600 SQUARE FOOT MANUFACTURING-DISTRIBUTION WAREHOUSE FACILITY WITH ASSOCIATED PARKING, TRUCK LOADING, STORM DRAINAGE DETENTION/WATER QUALITY BASINS AND UTILITIES.

3. THE ANTICIPATED START OF CONSTRUCTION IS PLANNED FOR THE SUMMER OF 2023 WITH FINAL COMPLETION IN APPROXIMATELY ONE YEAR.

CONSTRUCTION SEQUENCE -

THE SEQUENCE OF GRADING AND CONSTRUCTION ACTIVITIES WILL BE AS FOLLOWS:

1. CUT TREES AND REMOVE BRUSH WITHIN THE AREA OF CONSTRUCTION AND REMOVE OFF SITE.
- INSTALL CONSTRUCTION ENTRANCES.
- INSTALL GEOTEXTILE SILT FENCE.

2. CONSTRUCT EAST BASIN.

- STUMP AREA OF BASIN, STUMPS TO BE REMOVED FROM SITE. STUMPS ARE NOT TO BE BURIED ON THE PROPERTY.

- STRIP AND STOCKPILE TOPSOIL AT AREA OF EAST BASIN.

- EXCAVATE, GRADE, TOPSOIL AND SEED BASIN FOR TEMPORARY COVER. BASIN TO BE EXCAVATED TO ELEVATION 138.0 (2 FOOT ABOVE FINAL GRADE). SOIL BELOW THIS ELEVATION SHALL NOT BE DISTURBED.

- INSTALL PERMANENT STORM OUTLET STRUCTURE, FLARED END #9 AND CONNECTING PIPE.

- ORIFICE AT OUTLET STRUCTURE TO BE CORED AT COMPLETION OF CONSTRUCTION.

- PLACE RIP RAP PLUNGE POOL WHERE OUTLET PIPE DISCHARGES.

- INSTALL TEMPORARY OUTLET PIPE WITHIN BASIN.

- DURING SITE CONSTRUCTION, EAST BASIN SHALL FUNCTION AS A TEMPORARY SEDIMENT BASIN. AS NEEDED TEMPORARY SEDIMENT BASIN SHALL BE CLEANED OF ACCUMULATED SILT AND SEDIMENT SO THAT BASIN WILL FUNCTION PROPERLY THROUGHOUT THE DEVELOPMENT.

3. CONSTRUCT SOUTH BASIN.

- STUMP AREA OF BASIN, STUMPS TO BE REMOVED FROM SITE. STUMPS ARE NOT TO BE BURIED ON THE PROPERTY.

- STRIP AND STOCKPILE TOPSOIL AT AREA OF SOUTH BASIN.

- EXCAVATE, GRADE, TOPSOIL AND SEED BASIN FOR TEMPORARY COVER. BASIN TO BE EXCAVATED TO ELEVATION 138.0 (2 FOOT ABOVE FINAL GRADE). SOIL BELOW THIS ELEVATION SHALL NOT BE DISTURBED.

- INSTALL PERMANENT STORM OUTLET STRUCTURE, FLARED END #10 AND CONNECTING PIPE.

- ORIFICE AT OUTLET STRUCTURE TO BE CORED AT COMPLETION OF CONSTRUCTION.

- PLACE RIP RAP PLUNGE POOL WHERE OUTLET PIPE DISCHARGES.

- DURING SITE CONSTRUCTION, SOUTH BASIN SHALL FUNCTION AS A TEMPORARY SEDIMENT BASIN. AS NEEDED TEMPORARY SEDIMENT BASIN SHALL BE CLEANED OF ACCUMULATED SILT AND SEDIMENT SO THAT BASIN WILL FUNCTION PROPERLY THROUGHOUT THE DEVELOPMENT.

4. STUMP, STRIP AND STOCKPILE TOPSOIL FROM THE AREA OF THE BUILDING AND THE PROPOSED IMPROVEMENTS. PLACE GEOTEXTILE SILT FENCE AROUND STOCKPILED AREAS. PILES ARE TO BE SEADED FOR TEMPORARY VEGETATION IF PILE IS TO REMAIN FOR AN EXTENDED PERIOD OF TIME. STUMPS ARE TO BE REMOVED FOR THE PROPERTY.

5. GRADE THE AREAS OF THE PROPOSED IMPROVEMENTS.

6. BEGIN CONSTRUCTION OF BUILDING.

7. INSTALL STORM DRAINAGE.

- PLACE SILT SACK IN THE TOP OF NEW CATCH BASINS. AREAS AROUND NEW CATCH BASIN TOPS ARE TO BE DEPRESSED. THROUGHOUT CONSTRUCTION, CARE SHALL BE TAKEN TO KEEP DISTURBED SURFACE WATER FROM ENTERING THE CATCH BASINS.

8. CONSTRUCT UTILITIES, PAVEMENT AREAS AND OTHER SITE IMPROVEMENTS.

9. INSTALL PLANT MATERIAL.

10. LOAM AND SEED FOR PERMANENT COVER. IF PERMANENT COVER IS NOT DESIRED AT THE TIME OF THE SEEDING, USE TEMPORARY SEEDING FOR VEGETATIVE COVER SCHEDULE.

11. WHEN ALL CONTRIBUTING AREAS HAVE STABILIZED, ACCUMULATED SEDIMENT TO BE REMOVED FROM BASINS. REMOVE TEMPORARY OUTLET STRUCTURE AND PIPE. BLOCK AND SEAL PENETRATION INTO STRUCTURE. CORE PERMANENT ORIFICE. PLACE TOPSOIL AND SEED.

12. REMOVE ANY ACCUMULATED SEDIMENT ABOVE UNDER DRAIN PIPE IN DRY SWALES. REPLACE PERMEABLE SOIL IF NECESSARY TO PROVIDE FOR STORM WATER INFILTRATION.

13. THROUGHOUT CONSTRUCTION AND AT LEAST ONCE A WEEK, INSPECT GEOTEXTILE SILT FENCE AND/OR TEMPORARY VEGETATIVE COVER. IF REQUIRED, PERFORM MAINTENANCE AND REPAIRS TO ENSURE PROPER WORKING ORDER. GEOTEXTILE SILT FENCE FENCE IS TO REMAIN IN PROPER WORKING ORDER UNTIL ALL VEGETATIVE COVER HAS BEEN ESTABLISHED.


BEST REMOVAL OF ANY SILT FENCE, EXISTING ACCUMULATED SILT IS TO BE REMOVED AND DISPOSED OF PROPERLY. ALL DISTURBED AREAS ARE TO BE LOAMED AND SEADED TO ESTABLISH PERMANENT COVER.

14. THE OWNER OF THE PROPERTY AND/OR CONTRACTOR SHALL BE RESPONSIBLE FOR INSPECTION/MAINTENANCE/REPAIR/REPLACEMENT OF ALL EROSION CONTROL MEASURES UNTIL ALL CONTRIBUTING SURFACES HAVE BEEN ESTABLISHED.

Sheet
C6.2

SITE PLAN
PREPARED FOR
Condyne Capital Partners, LLC
EROSION & SEDIMENTATION CONTROL
NOTES AND DETAILS
WINDSOR, CONNECTICUT
205 BAKER HOLLOW ROAD



Alford
ASSOCIATES, INC.
CIVIL ENGINEERS
WINDSOR, CONNECTICUT
• WILSON M. ALFORD, JR., P.E. & L.S.
DATE: APRIL 20, 2023
SCALE: 1 IN. = FT.



NOT VALID WITHOUT A LIVE
SIGNATURE AND EMBOSSED SEAL

L.S. NO. 9344

L.S. NO. 9344





TO THE BEST OF MY
KNOWLEDGE AND BELIEF
THIS MAP IS SUBSTANTIALLY
CORRECT AS NOTED HEREON.

U.S. NO. 9344

**NOT VALID WITHOUT A LIVE
SIGNATURE AND EMBOSSED SEAL**

 TOWN OF WINDSOR
Engineering Department  DRAINAGE TRENCH
D-300

Engineering Department

DRAINAGE TRENCH
D-300

■ SCALE: HUR. NIS DATE: MAY 2010
VER.




The logo consists of two black star-like symbols with a lightning bolt through them, flanking the text "TOWN OF WINDSOR" and "Engineering Department".

TOWN OF WINDSOR
Engineering Department

CATCH BASIN TYPE "C"
PRECAST CONCRETE

The logo consists of two black starburst icons flanking the text "TOWN OF WINDSOR" and "Engineering Department".

CATCH BASIN TOP
TYPE "C" PRECAST CONCRETE



SITE PLAN

PREPARED FOR

Condyne Capital Partners, LLC

STORM DRAINAGE

NOTES AND DETAILS

WINDSOR CONNE

EB HOLLOW ROAD

2006 DAVE

Sheet
C6.3



TO THE BEST OF MY
KNOWLEDGE AND BELIEF
THIS MAP IS SUBSTANTIALLY
CORRECT AS NOTED HEREON.

L.S. NO. 9344

NOT VALID WITHOUT A LIVE
SIGNATURE AND EMBOSSED SEAL






CIVIL ENGINEERS
WINDSOR, CONNECTICUT
•
WILSON M. ALFORD, JR., P.E. & L.S.


DATE: APRIL 20, 2023

SCALE: 1 IN. = FT.

SITE PLAN
PREPARED FOR
Condyne Capital Partners, LLC
STORM DRAINAGE AND UTILITIES
NOTES AND DETAILS
WINDSOR, CONNECTICUT
205 BAKER HOLLOW ROAD

Sheet
C6.4





WB-50 VEHICLES ENTERING FROM EAST, EXITING TO WEST

BAKER HOLLOW ROAD


N/F ONE HUNDRED FIVE HOLLOW ROAD INVESTORS LLC
#105 BAKER HOLLOW RD
(VOL. 1925, PG. 799)

MATCH
SEE SHEET 7.1

MATCH

GRAPHIC SCALE

(IN FEET)
inch = 40 ft




LOCATIONS OF UNDERGROUND UTILITIES ARE APPROXIMATE AND ALL
LINES MAY NOT BE SHOWN. PRIOR TO CONSTRUCTION, CONTRACTOR SHALL
CALL 1-800-922-4455 AND HAVE UTILITIES MARKED ON THE GROUND.

Sheet
C7.0

וְכֹא כָּא , עַיִינֵינוּ מִכְמֵנוּ , בְּאֵין

۱۷۵



THE BEST OF MY
KNOWLEDGE AND BELIEF
THIS MAP IS SUBSTANTIALLY
CORRECT AS NOTED HEREON

L.S. NO. 9344

Alford
ASSOCIATES INC.

CIVIL ENGINEERS
WINDSOR, CONNECTICUT
●
WILSON M. ALFORD, JR., P.E. & L.S.

TE:APRIL 20, 2023

ALE: 1 IN. = 40 FT

L

PLA/
ers,

CHIEF LEAN PREPARED FOR capital Part LEARNING MOVEMENT

ndyne
TRUCK


०

Sheet


SEE SHEET 7.0

MATCH

R REALTY LLC
FOLLOW RD
PG. 1136)



WB-50 VEHICLES ENTERING FROM WEST, EXITING TO EAST



REVISION
DATE



TO THE BEST OF MY
KNOWLEDGE AND BELIEF
THIS MAP IS SUBSTANTIALLY
CORRECT AS NOTED HEREON.

L.S. NO. 9344

NOT VALID WITHOUT A LIVE
SIGNATURE AND EMBOSSED SEAL

Alford
ASSOCIATES, INC.

CIVIL ENGINEERS
WINDSOR, CONNECTICUT
•
WILSON M. ALFORD, JR., P.E. & L.S.

DATE: APRIL 20, 2023

SCALE: 1 IN. = 40 FT.


SITE PLAN
PREPARED FOR
Condyne Capital Partners, LLC
TRUCK TURNING MOVEMENT PLAN
WINDSOR, CONNECTICUT

N/F SPC
#800 L
(VO)
205 BAKER HOLLOW ROAD


WB-50 VEHICLES ENTERING PARKING AREA

INVESTORS LLC

BAKER HOLLOW ROAD




GRAPHIC SCALE



Sheet
C7.1

THE LOCATIONS OF UNDERGROUND UTILITIES ARE APPROXIMATE AND ALL
UTILITIES MAY NOT BE SHOWN. PRIOR TO CONSTRUCTION, CONTRACTOR SHALL
CALL 1-800-922-4455 AND HAVE UTILITIES MARKED ON THE GROUND.



GENERAL DISCLAIMER

GENERAL DISCLAIMER:
Calculations have been performed according to IES standards and good practice. Some differences between measured values and calculated results may occur due to tolerances in calculation methods, testing procedures, component performance, measurement techniques and field conditions such as voltage and temperature variations. Input data used to generate the attached calculations such as room dimensions, reflectances, furniture and architectural elements significantly affect the lighting calculations. If the real environment conditions do not match the input data, differences will occur between measured values and calculated values.

input data, differences will occur between measured value

* LLF Determined Using

NOTE TO REVIEWER:
Total Light Loss Factor (LLF) applied at time of design is determined by applying the Lamp Lumen Depreciation (LLD) from current lamp manufacturer's catalog, a Luminaire Dirt Depreciation Factor (LDD) based on IES recommended values and a Ballast Factor (BF) from current ballast specification sheets. Application of an incorrect Light Loss Factor (LLF) will result in forecasts of performance that will not accurately depict actual results.

will not accurately depict actual results.
For proper comparison of photometric layouts, it is essential that you insist



LIGHTING SOLUTION

20-30 BEAVER ROAD, WETHERSFIELD, CT 06104
TEL/FAX 860.632.8766 / WWW.APEXI.TG.COM

PROJECT TITLE

205 BAKER HOLLOW ROAD
CONDYNE
WINDSOR, CT

DRAWING TITLE:
SITE LIGHTING
PHOTOMETRIC CALCULATION

SCALE : 1"=60'-0"

DATE: 5/2/23

DRAWN BY: LED/PD

SHEET:

SL-1