

**TECHNICAL SPECIFICATION 240
BITUMINOUS CONCRETE CURBING**

240.1 SCOPE OF WORK

This technical specification covers the furnishing of all labor, materials, testing, submittals, tools, and equipment necessary to construct and place machine formed bituminous concrete lip curbing, bituminous concrete flat top curb, or bituminous concrete Cape Cod curbing in accordance with the dimensions and details as shown on the plans or as directed by the Engineer.

240.2 MATERIALS

Materials, including tack coat, for the work shall conform to the requirements of Form 817, Section M.04, Curb Mix or Bituminous Class 3.

240.3 SUBMITTALS

Not applicable.

240.4 CONSTRUCTION METHODS

The bituminous concrete curbing shall be placed in accordance with Form 817, Section 8.15.03. In new construction, it shall be placed on the binder course. Prior to the placement of the bituminous concrete curbing, the area shall be cleaned of all loose and foreign materials, and a tack coat shall be applied.

240.5 MEASUREMENT

Measurement for this item will be based on the number of linear feet of specified bituminous concrete curbing placed and accepted.

240.6 PAYMENT

Payment for this item will be based the contract unit price per Linear Foot complete and accepted in place, including all labor, materials, testing, submittals, tools, and equipment necessary to complete the work as specified.

| PAY ITEM | PAY UNIT |
|---------------------------------|-----------------|
| Bituminous Concrete (Type) Curb | L.F. |