

**TECHNICAL SPECIFICATION 245
CONCRETE CURBING**

245.1 SCOPE OF WORK

This technical specification covers the furnishing of all labor, materials, testing, submittals, tools, and equipment necessary to construct and place concrete curbing on a prepared base, in accordance with the dimensions and details as shown on the plans or as directed by the Engineer.

245.2 MATERIALS

Materials shall conform to Form 817, Section 8.11.02.

Processed aggregate shall be medium gradation conforming to Technical Specification 210 – “Processed Aggregate Base”.

245.3 SUBMITTALS

The following submittals shall be submitted to the Engineer for review and approval prior to installation:

- Concrete specifications from supplier
- Material certifications for all pre-cast concrete
- Gradation test results for processed aggregate

245.4 CONSTRUCTION METHODS

Concrete curbing shall be placed in accordance with Form 817, Section 8.11.03.

245.5 MEASUREMENT

Measurement for this item will be based on the number of linear feet of concrete curbing placed and accepted.

245.6 PAYMENT

Payment for this item will be based on the contract unit price per Linear Foot completed in place, including all labor, materials, testing, submittals, tools, and equipment necessary to complete the work as specified.

PAY ITEM	PAY UNIT
Concrete Curbing (Type)	L.F.