

**TECHNICAL SPECIFICATION 205
BANK RUN GRAVEL**

205.1 SCOPE OF WORK

This technical specification covers the furnishing of all labor, materials, testing, submittals, tools, and equipment necessary to properly place and compact gravel to correct grades at all locations where shown on the drawings or as directed by the Engineer.

205.2 MATERIALS

All materials used under this item shall conform to Form 817, Section M.02.02 and M.02.06. Reclaimed or recycled materials will not be accepted.

205.3 SUBMITTALS

The following submittals shall be submitted to the Engineer for review and approval prior to installation:

- Gradation test results for bank run gravel

205.4 CONSTRUCTION METHODS

Work under this technical specification shall conform to Form 817, Section 2.12.03.

205.5 MEASUREMENT

Measurement for this item will be based on the number of cubic yards compacted and accepted in place.

205.6 PAYMENT

Payment for this item will be based on the contract unit price per Cubic Yard, completed, compacted, and accepted in place, including all labor, materials, testing, submittals, tools, and equipment necessary to complete the work as specified.

PAY ITEM	PAY UNIT
Bank Run Gravel	C.Y.