

**TECHNICAL SPECIFICATION 215
PROCESSED AGGREGATE DRIVES**

215.1 SCOPE OF WORK

This technical specification covers the furnishing of all labor, materials, testing, submittals, tools, and equipment necessary to properly place processed aggregate for drives in conformance with lines, grades and compacted depths shown on the plans.

215.2 MATERIALS

All material for processed aggregate drives shall be medium gradation conforming to Technical Specification 210 – “Processed Aggregate Base”. Gravel and reclaimed processed aggregate will not be accepted.

215.3 SUBMITTALS

The following submittals shall be submitted to the Engineer for review and approval prior to installation:

- Gradation test results for processed aggregate

215.4 CONSTRUCTION METHODS

The processed aggregate shall be placed in conformance with Form 817, Section 3.04.03, in 4 inch lifts, with a maximum compacted thickness of 4 inches for residential drives and 8 inches for parking areas.

215.5 MEASUREMENT

Measurement for this item will be based on the number of square yards compacted in place within the construction limits, as determined by the Engineer.

215.6 PAYMENT

Payment for this item will be based on the contract unit price per Square Yard, completed in place, including all labor, materials, testing, submittals, tools, and equipment necessary to complete the work as specified.

PAY ITEM	PAY UNIT
Processed Aggregate Drive (Type)	S.Y.