

**TECHNICAL SPECIFICATION 420
PLANTINGS**

420.1 SCOPE OF WORK

This technical specification covers the furnishing of all labor, materials, testing, submittals, tools, and equipment necessary to furnish and install plantings in accordance with the plans and detail drawings. The work shall include excavation, furnishing and installing the planting, backfill, fertilizer, edging, mulch, watering, weed control mats, stakes and all miscellaneous items.

420.2 MATERIALS

Material for this work shall conform to the requirements of Form 817, Section M.13, as specified.

420.3 SUBMITTALS

The following submittals shall be submitted to the Engineer for review and approval prior to installation:

- Source of supply for plant material shall be provided at least one month prior to planting

420.4 CONSTRUCTION METHODS

Construction methods used for this section shall be in accordance with Form 817, Section 9.49, as may be amended on the plans and detail drawings. All plantings shall be thoroughly watered during backfilling and within 48 hours after planting, if conditions warrant. Subsequent waterings and care shall be performed by the Contractor to comply with the provisions of Form 817, Section 9.49.03.17, Establishment Period.

420.5 MEASUREMENT

Measurement for this item will be based on the actual number of each type and size of planting counted in place, planted and accepted.

420.6 PAYMENT

Payment for this item will be based on the contract unit price Each for the type and size planting completed and accepted in place, including all labor, materials, testing, submittals, tools, and equipment necessary to complete the work as specified.

PAY ITEM	PAY UNIT
Plant (type/size)	EA.