

**TECHNICAL SPECIFICATION 436
CONSTRUCTION FENCING**

436.1 SCOPE OF WORK

The purpose of this technical specification is to cover the furnishing of all labor, materials, testing, submittals, tools, and equipment necessary to furnish and install construction fencing, as shown on the plans, or as directed by the Engineer.

436.2 MATERIALS

Construction fencing shall be 4 foot high, green plastic, similar to Visi-Barrier, or equal.

436.3 SUBMITTALS

The following submittals shall be submitted to the Engineer for review and approval prior to installation:

- Manufacturer(s) cut sheet(s) for fencing materials

436.4 CONSTRUCTION METHODS

Construction fencing for shall be installed in accordance with the plans and as directed by the Engineer.

436.5 MEASUREMENT

Measurement for construction fencing will be based on the actual number of linear feet of chain link fence completed and accepted. Minor relocations of the construction fencing to accommodate construction, or at the Town's request, shall be performed by the Contractor at no additional cost. Any relocation of fencing over 100 feet per occurrence shall be reimbursed by the Town at the unit price bid.

436.6 PAYMENT

Payment for these items will be based on the contract unit price per Linear Foot for construction fencing, including all labor, materials, testing, submittals, tools, and equipment necessary to complete the work as specified.

PAY ITEM	PAY UNIT
Construction Fencing	L.F.